



ADDENDUM NO 1

Issued on Sept 13, 2022

Project No ITB 0213

**44th St Sidewalk between
4605 SE 44th & Mickey Rd**

1. Page 21 Item 3 under: BIDDERS PROPOSAL
Change of Sq yds concrete from 225 to 150 yds
Please submit bid for Item 3 at 150 yds concrete

Resident Driveway replacement / modification to establish
ADA cross-slope or replace broken concrete – 4” of 3500#
Concrete on 4” of compacted 1 1/2” crusher run

*****END OF ADDENDUM NO 1*****